



Pennsylvania Contractor License PA088238

RECEIPT Prepared for:

Jacquie Walker
956 Bypass Rd
Perkasie, PA

Description:

Total due from Invoice dated 6/15/2021

\$5,450.00

Check received for this amount rec'd 6/18/21

PAID IN FULL (6/18/21)

Thank you!!

Jon Stockton

Stockton Contracting
23 S. 9th St
Quakertown, PA 18951
(610) 462-7791

Date: 6/18/21

(215) 693-4209

jacquie.walker2013@gmail.com



Pennsylvania Contractor License PA088238

Stockton Contracting
23 S. 9th St
Quakertown, PA 18951
(610) 462-7791

jstocktoncbc@verizon.net

ESTIMATE Prepared for:

Jacquie Walker
956 Bypass Rd
Perkasie, PA

Date: 2/12/2021

(215) 693-4209

jacquiewalker2013@gmail.com

Slate Roof Repair (Rear/pool side of house only)

*NOTE: Snow/Ice ripped down gutter, broke crown molding, broke broad-board decking at bottom edge, and damaged slates, also slates in roof field. Only correct fix is to remove all to second slate row and begin again; with less overlap and correctly hung gutters. Snow guards are highly recommended to prevent future failure (recommend 2 rows at minimum, price not included here).

- 1) Remove existing half-round gutters and hangers
- 2) Remove existing crown molding fascia/soffit detail
- 3) Remove starter course and first 2 courses slate
- 4) Repair broken broadboard decking at bottom edge
- 5) Correctly install new crown molding/fascia detail (painted)
- 6) Correctly install new half-round gutter hangers, gutters, and spout
- 7) Install slates at correct overlap (starter row and first 2 rows)
- 8) Repair broken/lose/missing slates in roof field (up to 20 pieces)
- 9) Remove debris
- 10) Includes emergency temporary repair (\$400, pd 2/10/21)

Total Cost: \$8,550.00

50% due before project start, balance due on completion

Note: Any additional carpentry, material, labor, etc., is extra

ALL PROJECTS PERFORMED IN COMPLIANCE WITH
INDUSTRY STANDARDS

Please call or email with any questions!

Thanks, Jon Stockton